

**Development of Jalgaon Goods Shed (as brown –field project) through private investment (as a Common User facility with maintenance of existing infrastructure and provision of new infrastructure) for a period of 06 years (01 year for completion of construction work and further 05 years for sharing of revenue (Terminal charge), from the date of completion of work)**

Open e- tender with two packet system (technical bid and financial bid) is uploaded on [www.ireps.gov.in](http://www.ireps.gov.in) on 30.12.2020 . Interested and experienced bidders can participate in this tender. NIT with tender document can be downloaded from this site -[www.ireps.gov.in](http://www.ireps.gov.in)

**Tender closing date is – 25.01.2021 at 15:00 hrs**

**Pre-bid meeting is scheduled on - 08.01.2021 at 16:00 hrs**

Address of pre-bid meeting -

Divisional Railway Manager (Commercial)  
Commercial Department,  
Divisional Railway Manager's Office,  
Central Railway, Bhusawal– 425201  
**Contact No. 02582 - 222433**

## **SCOPE OF WORK:**

At Jalgaon there are two goods sheds namely New Goods shed (NGS) and New Rail level (NRL). The following improvement and creation of additional facilities to be under taken at Jalgaon goods shed as brown-field project:

S.No.	Description of work	Approx.Area (Sqm)
1	Jalgaon (NRL)-Provision of Goods covered shed(325x10m=3250m <sup>2</sup> ) at New Rail Level Goods Platform at Jalgaon.(Without side sheeting for Half rake handling capacity)	325x10=3250m <sup>2</sup>
1.1	Electricity portion for proposed shed	325x10=3250m <sup>2</sup>
2	Jalgaon (NRL)- Development of Additional goods shed circulating area at New Rail level Platform by concreting at Jalgaon. (Concrete flooring)	325x10=3250m <sup>2</sup>
3	Jalgaon-Repairs to flooring of NGS shed & approach road of Surat end of NRL at Jalgaon. (Concrete flooring)	5850m <sup>2</sup>
4	Jalgaon (NRL):-Provision of Goods office size-5x4m,Merchant Room size-5x4m, Labour Room-7x4m & Toilet Block-2.5x6.56m.(With basic amenities) at New rail Level Goods shed at Jalgaon.	150m <sup>2</sup>
4.1	Electricity portion for proposed Goods office, Merchant room, Labour room and basic amenities.	150m <sup>2</sup>
5	Provision of precoated galvanized iron profile sheets (PPGI) Side sheeting (900 m long & 4 m height) on existing boundary wall of NGS Jalgaon to arrest dust.	900 x 4 = 3600m <sup>2</sup>

**Existing Facilities at Jalgaon Goods Sheds (New Goods Shed (NGS) and New Rail level (NRL))**

Working Hrs	Round the clock				
No. of Goods Shed	02 i.e New Goods Shed (NGS) and New Rail level (NRL)				
Avg. No. of rakes dealt/ month (including NGS & NRL)	30 rakes i.e 75000 Tonnes per month				
Commodities handled	Inward – Cement, Fertilizers & Food grains Outward - Maize				
Existing Capacity	Spur	High Level PF at NGS		Rail Level PF at NRL	Total
		Capacity of wagons placed on Open shed	Capacity of wagons placed on Covered shed	Shed not available at this goods shed	
	I	06	12 (190 mtr)	--	18
	II	20	22 (350 mtr)	--	42
	III	--	--	42	42
Circulating area & approach road	I & III -Concrete. II – Partly concrete + asphalting				
Lighting arrangement	Adequate at both NGS and NRL				
Basic facilities (G/shed office, Merchants/ Labours Room, drinking water etc.)	Available near high level G/shed at NGS				
Existing Works in progress	1. 41 doors of New Goods shed have been replaced and repaired. 2. Work of approach road at NGS is under progress.				